

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CONSERVATION DIVISION
WICHITA, KANSAS

JAN 16 1967
1-16-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Fred Damme of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Damme guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company

Complete Address: Fifth Floor, Ritz Bldg., Tulsa, Oklahoma

Lease Name: Elsie Omo Well No. # 1-A

Location: App. SE SE NE Sec. 35 Twp. 28 Rge. 14 (E)(W) W

County Pratt Total Depth 4646' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Damme was instructed to plug the well as follows:

308' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Aubie Elving
Conservation Division Agent