

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 30 1963
 9-30-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Ed Walker of Garvey Drilling Co. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Mayflo Oil Co.

Complete Address: 1435 Republic National Bank Bldg., Dallas 1, Tex.

Lease Name: Elsie Omo Well No. # 1-35

Location: SE NW NE Sec. 35 Twp. 28 Rge. 14 (E) (W) W

County Pratt Total Depth 4497 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

790' of 8 5/8" surface pipe, cemented with 500 sacks.

Fill hole with drilling mud to 300', 1st cementing plug,

1/2 sack hulls, cement with 25 sacks. Fill hole with drill-

ing mud to 40', 2nd cementing plug, 1/2 sack hulls, cement

with 10 sacks to base cellar. Bridge and cement rat hole

with 2 sacks.

Very truly yours,

Archie Ewing
 Conservation Division Agent