



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 30 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Catt of Kathol Pet. Inc has this
date requested permission to plug the following described well:

Mr. Catt guarantees payment of the plugging fee.

Operator's full Name: Kathol Petroleum Inc

Complete Address: 900 Sutton Place Wichita, KS

Lease Name: Howell Well No. 1

Location: SE/SE/NE Sec. 11 Twp. 29s Rge. 16 (E)(W) W

County: Kiowa Total Depth 4562 Oil Well

Gas Well Input Well SWD Well ~~D & A~~ OWWO ✓

Mr. Catt was instructed to plug the well as follows:

446 ft 8 5/8 surface cement circulated. Fill hole to
350 ft, plug, 1/2 sack hulls, 35 sacks cement. Mud to 40 ft,
plug, 1/2 sack hulls, 10 sacks cement to surface. 2 sacks
cement in rat hole.

Very truly yours,

[Signature]
Conservation Division Agent