

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 MAY 15 1967
 5-15-67
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Intent to Drill,
 filed April 25, 1967.

Dear Sir:

Mr. Herman Johnson of Gabbert-Jones, Inc. has this
 date requested permission to plug the following described well:

Mr. Johnson guarantees payment of the plugging fee.

Operator's full Name: Pan-Western Petroleum, Inc.

Complete Address: 404 One Twenty Bldg., Wichita, Kansas 67202

Lease Name: McClure-Breidenthal Well No. # 1

Location: C NE SE Sec 20 Twp. 29 Rge. 16 (E)(W) W

County Kiowa Total Depth 4783' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Johnson was instructed to plug the well as follows:

270' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill
hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Audie Elving
 Conservation Division Agent