

State of Kansas



FORM - CP-2

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSASVERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSIONMAR 11 1964  
3-11-64  
CONSERVATION DIVISION  
Wichita, KansasJ. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Don Murray of Tommy Ward Drilling Co. has this  
date requested permission to plug the following described well:Mr. Murray guarantees payment of the plugging fee.Operator's full Name: James F. SmithComplete Address: Box 10005, Amarillo, TexasLease Name: Conklin Well No. # 1-9Location: C NE NE Sec. 9 Twp. 29 Rge. 17 (E) (W) WCounty Kiowa Total Depth 4834 Oil Well Gas Well  Input Well  SWD Well  D & A X Lost Hole Mr. Murray was instructed to plug the well as follows:

420' of 8 5/8" surface pipe, cemented with 275 sacks. Fill  
with drilling mud to 340', 1st cementing plug, bridge with  
hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge and cement with 10  
sacks to base cellar. Bridge and cement rat hole with 2  
sacks.

Very truly yours,

Archie Elving  
 Conservation Division Agent