

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
CORPORATION COMMISSION
OCT 20 1967
10-30-67
CONSERVATION DIVISION
WICHITA, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed October 17, 1967.

Dear Sir:

Mr. Norman Thompson of Garvey Drilling Company has this date requested permission to plug the following described well:

Mr. Thompson guarantees payment of the plugging fee.

Operator's full Name: William Grunerwald & Assoc., Inc.

Complete Address: P. O. Box 909, Colorado Springs, Colorado 80900

Lease Name: Haskins Well No. # 1

Location: C NW SE Sec. 7 Twp. 29 Rge. 13 (E) (W) W

County Pratt Total Depth 4651 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Thompson was instructed to plug the well as follows:

820' of 8 5/8" surface pipe, cement circulated with 400 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat & mouse holes with 4 sac

Very truly yours,

Archie Elving
Conservation Division Agent