

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

APR 1 1963

CONSERVATION DIVISION
 WICHITA, KANSAS

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Gould of Barnett Oil Co. has this

date requested permission to plug the following described well:

Mr. Gould guarantees payment of the plugging fee.Operator's full Name: Barnett Oil Co.Complete Address: 411 1st National Bank Bldg., Wichita, KansasLease Name: Bass Well No. # 1Location: SW NW NW Sec. 7 Twp. 29 Rge. 13 (E) (W) WCounty Pratt Total Depth 4700 Oil Well XGas Well Input Well SWD Well D & A Lost Hole Mr. Gould was instructed to plug the well as follows:

840' of 8 5/8" surface pipe cement circulated. Fill hole
with drilling mud to 240', 1st cementing plug, 1/2 sack hulls,
20 sacks cement. Fill hole with mud to 40', 2nd cementing
plug, 1/2 sack hulls, cement with 10 sacks to base cellar.
Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent