

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

MAR 11 1964
3-11-64
CONSERVATION DIVISION
Wichita, Kansas

Dear Sir:

Mr. Bill Orr of Thunderbird Drilling Inc. has this date requested permission to plug the following described well:

Mr. Orr guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling Inc.

Complete Address: 706 Union Center, Wichita, Kansas

Lease Name: McBurney Well No. # 1

Location: C NW NW Sec. 20 Twp. 27 Rge. 7 (E) (W) W

County Kingman Total Depth 4340 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Orr was instructed to plug the well as follows:

282' of 8 5/8" surface pipe, cemented with 200 sacks. Fill hole with drilling mud to 275', 1st cementing plug, bridge with hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with hulls, and cement with 10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent