

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
1967

SEP 18 1967

9-18-67

CONSERVATION DIVISION  
Wichita, Kansas

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill;  
filed August 29, 1967.

Dear Sir:

Mr. Webster Hill of Mack Oil Company has this  
date requested permission to plug the following described well:

Mr. Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas 67202

Lease Name: Dickerson Well No. # 1

Location: C NE SW Sec. 20 Twp. 27 Rge. 7 (E)(W) W

County Kingman Total Depth 4350' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Hill was instructed to plug the well as follows:

270' of 8 5/8" surface pipe, cement circulated with 250 sacks. Fill hole with drilling mud to 260', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat and mouse holes with 4 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent