

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAR 8 1967

3-8-67

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Intent to Drill, filed
 February 24, 1967.

Dear Sir:

Mr. Jack Gabbert of Gabbert-Jones, Inc. has this
 date requested permission to plug the following described well:

Mr. Gannert guarantees payment of the plugging fee.

Operator's full Name: Thunderbird Drilling, Inc.

Complete Address: 400 North Woodlawn, Suite 7, Wichita, Kansas

Lease Name: Wilkinson Well No. # 1

Location: C NE NE Sec. 8 Twp. 27 Rge. 6 (E)(W)W

County Kingman Total Depth 4083' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Gabbert was instructed to plug the well as follows:

267' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill
hole with drilling mud to 260', 1st cementing plug, bridge with 1/2 sack
hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent