

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
 STATE CORPORATION COMMISSION

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

OCT -2 1967

10-2-67

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Intent to Drill,
 filed August 29, 1967

Dear Sir:

Mr. Webster Hill of Mack Oil Company has this
 date requested permission to plug the following described well:

Mr. Hill guarantees payment of the plugging fee.

Operator's full Name: Mack Oil Company

Complete Address: 812 Union Center Bldg., Wichita, Kansas 67202

Lease Name: Biggs Well No. # 1

Location: C SE SE Sec. 5 Twp. 27 Rge. 6 (E)(W) W

County Kingman Total Depth 4100' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hill was instructed to plug the well as follows:

247' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill
hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge & cement rat & mouse holes with 4 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent