

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

OCT 19 1964
 10-19-64
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

10-8-64

Dear Sir:

Mr. Voth of Knight Casing Pulling Company has this date requested permission to plug the following described well:

Mr. Voth guarantees payment of the plugging fee.

Operator's full Name: Drillers Production Company Incorporated

Complete Address: 1020 Union National Building, Wichita, KANSAS

Lease Name: Opdyke Well No. #2

Location: C-SW-SW Sec. 28 Twp. 27 Rge. 5 (E) (W) X

County Kingman Total Depth 3782 Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Voth was instructed to plug the well as follows:

250 feet of 8 5/8 inch surface pipe cement circulated; 3782 feet of 4 1/2
inch long string cemented with 100 sacks; sand to 3760, cemented with 3
sacks; mud to 250 feet, 10 feet rock bridge and cemented with 25 sacks;
mud to 40 feet, 10 feet rock bridge and 10 sacks cement to base of cellar.

Very truly yours,

Conservation Division Agent