

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Voet of The Shallow Water Refining Company ^{financing} ~~is~~ ^{has this}

date requested permission to plug the following described well:

Mr. Voet guarantees payment of the plugging fee.

Operator's full Name: The Shallow Water Refining Company

Complete Address: 1325 Wichita Plaza. Wichita, Kansas

Lease Name: Bartholomew Unit Tract 8 Well No. # 1

Location: SE SW NW Sec. 31 Twp. 27S Rge. 4 (A) (W)

County Sedgwick Total Depth 3772' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Voet was instructed to plug the well as follows:

8 5/8"-277'-Circulated w/cement. 5 1/2"-3767'-Cemented. Sand hole to 3750'.

5 Sax. cement 3750' to 3700'. Mud 3700' to 360'. Bridge 360' to 340'.

5 Yds. cement 340' to 0. Pulled 3220' 5 1/2"-pipe.

RECEIVED
STATE CORPORATION COMMISSION

Very truly yours,

SEP 27 1967
9-27-67
CONSERVATION DIVISION
Wichita, Kansas

Hugh Scott
Conservation Division Agent