

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-095-20788-00-00  
Spot: SE Sec/Twnshp/Rge: 5-27S-6W  
1320 feet from S Section Line, 1320 feet from E Section Line  
Lease/Unit Name: WALLACE Well Number: 1  
County: KINGMAN Total Vertical Depth: 4308 feet

Operator License No.: 4419  
Op Name: BEAR PETROLEUM, INC.  
Address: PO BOX 438  
HAYSVILLE, KS 67060

Production Casing Size: 7 feet: 4307  
Surface Casing Size: 10.75 feet: 267

140'

Well Type: OG UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/19/2003 9:00 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTY JOE Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: Sand to 3700' & 7 sacks. 35 sacks @ 1000'. 35 sacks @ 500'. 317' to 0'.

RECEIVED  
KCC DISTRICT #2  
AUG 29 2003  
8-29-03  
WICHITA, KS

Plugging Proposal Received By: JACK LUTHI

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 08/19/2003 4:00 PM

KCC Agent: JACK LUTHI

**Actual Plugging Report:**

Sanded bottom to 3700' and 7 sacks of common. Shot 7" casing off at 2702'. Pulled to 1000'. Pumped 65 sacks and 100 lbs of hulls. Pulled to 500'. Pumped 65 sacks and 100 lbs of hulls. Pulled to 317'. Circulated cement to surface.

Remarks: COPELAND CEMENT 60/40 4%

Plugged through: CSG

District: 02

Signed

Jack Luthi  
(TECHNICIAN)

INVOICED

DATE

9-9-03

INV. NO.

2004060487