

1 010214

84

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,826-65-00  
150' E S/2  
S/2 S/2 NW/4SEC. 19, T 28 S, R 15 ~~W/4~~

2970 feet from S section line

3860 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5237

Lease Name Gross Well # 2

Operator: Plano Petroleum Corporation

County Pratt 155.84

Name & Address P.O. Box 247

Well Total Depth 4795 feet

Plano, Texas 75074

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 351

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Brandt Drilling Co. License Number 5840

Address 105 South Broadway, #920, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 13 Month: 2 Year: 19 87

Plugging proposal received from Jack Kaiser

(company name) Brandt Drilling Company (phone) 316-267-4335

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1030'  
1st plug at 1050' with 50 sx cement, 2nd plug at 360' with 40 sx cement,  
3rd plug at 40-0' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,  
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:45 a.m. Day: 13 Month: 2 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 1050' with 50 sx cement,

2nd plug at 360' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

**INVOICED**

DATE 2-20-87

INV. NO. 16186

STATE CORPORATION COMMISSION  
FEB 19 1987  
CONSERVATION DIVISION  
Wichita, Kansas

Signed Jack Kaiser  
(TECHNICIAN)  
2-19-87

CARD MUST BE TYPED

State of Kansas

CARD MUST BE SIGNED

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Starting Date February 6, 1987 month day year

API Number 15-151-21,826-00-00 150' E S/2 S/2 NW1/4 Sec. 19 Twp. 28 S, Rg. 15 West 2970 Ft. from South Line of Section 3860 Ft. from East Line of Section

OPERATOR: License # 5237 Name Plano Petroleum Corporation Address P.O. Box 247 City/State/Zip Plano, Texas 75074 Contact Person K. Fletcher Phone 214/422-4995

(Note: Locate well on Section Plat on reverse side) Nearest lease or unit boundary line 330 feet County Pratt

CONTRACTOR: License # 5840 Name Brandt Drilling Co., Inc. City/State Wichita, Kansas 67202

Lease Name GROSS Well # 2 Ground surface elevation 2110 feet MSL Domestic well within 330 feet: yes X no Municipal well within one mile: yes X no

Well Drilled For: Well Class: Type Equipment: X Oil SWD Infield Mud Rotary Gas Inj X Pool Ext Air Rotary OWWO Expl Wildcat Cable

Depth to bottom of fresh water 200 Depth to bottom of usable water 200-300 Surface pipe by Alternate: 1 X 2 Surface pipe planned to be set 330

If OWWO: old well info as follows: Operator Well Name Comp Date Old Total Depth

Conductor pipe required Projected Total Depth 4800 Formation Kinderhook

I certify that well will comply with K.S.A. 55-101, et seq, plus eventually plugging hole to KCC specifications. Date 2-5-87 Signature of Operator or Agent Title Agent

For KCC Use: Conductor Pipe Required feet; Minimum Surface Pipe Required 300 feet per Alt. This Authorization Expires 8-5-87 Approved By 2-5-87

879-2-5-87-300 12 1/4- Jack Kaiser

JACK KAISER

Sec. Twp. S, Rg. West

316-255-3055

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting surface casing (call 7 a.m. to 5 p.m. workdays).

1st plug @ 9'0" feet depth with 60-40 sx of 2nd plug @ 3'50" feet depth with 60-40 sx of 3rd plug @ 4'50" feet depth with 60-40 sx of 4th plug @ 4'00" feet depth with 60-40 sx of 5th plug @ 1'00" feet depth with 60-40 sx of (2) Rathole with backfill well (b) Mousehole with

PUSHER JACK KAISER TD 4650 FORMATION MISS SURFACE PIPE @ 351 ANHYDRITE 1030 ELEVATION STARTING TIME & DATE COMPLETION TIME & DATE 1st PLUG @ 1050 FT. W/ 50 SX 2nd PLUG @ 360 FT. W/ 40 SX 3rd PLUG @ 40-0 FT. W/ 10 SX 4th PLUG @ FT. W/ SX RAT HOLE CIRCULATED W/ 15 SX MOUSE HOLE CIRCULATED W/ 10 SX WATER WELL PLUGGED W/ WATER WELL-SX CEMENT COMPANY TECHNICIAN

STATE CORPORATION COMMISSION FEB 10 1987 CONSERVATION DIVISION Wichita, Kansas