

1090082

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,397-00-00
100' W & 100' S
of C NE NE, SEC. 16, T. 28 S, R. 15 W/EX
4520 feet from S section line
760 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5030
Operator: Vess Oil Corporation
Name & Address 8100 E. 22nd St. N, Bldg. 300
Wichita, KS 67226

Lease Name Keller Well # 1-16
County Pratt 15/28
Well Total Depth 4655 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 357

Abandoned Oil Well Gas Well Input Well SHD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 28 Month: 5 Year: 19 91

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 4654' w/150 sx cement, PBTD 4610', Perfs at 4552-55'

1st plug sand back to 4500' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 2 p.m. Day: 28 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 4500' and dumped 4 sx cement on top of
sand through Bailer,

2nd plug pumped 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,
released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 800 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2736' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

Signed [Signature] (TECHNICIAN)

DATE 6-18-91

INV. NO. 32179

RECEIVED
STATE CORPORATION COMMISSION
6-7-91
JUN 07 1991