

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151- 21,390 -00-06

C N/2 NW NW Sec. 15 , T 28 S, R 15 W/4

330 feet from N/SX section line

330 feet from W/SX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5021

Lease Name Henry Well # 1-15

Operator: Imperial Oil Company
Name & 720 Fourth Financial Center
Address Wichita, KS 67202

County Pratt

Well Total Depth 4629 feet 150.44

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 444

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Red Tiger Drilling Co. License Number 5302

Address 1720 Kansas State Bank Building, Wichita, KS 67202

Company to plug at: Hour: 6:00 pm Day: 20 Month: January Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Mike Remple

(company name) Red Tiger (phone) 316-263-5205

wereto fill hole with heavy mud and spot cement through drill pipe.

1st plug at 990' with 50 sx cement

2nd plug at 480' with 50 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate the rathole with 10 sx cement. Plug water well with

5 sx cement.

Signed Steve Rement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 8:30 pm Day: 20 Month: January Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 990' with 50 sx cement, 2nd plug at 480' with 50 sx cement, 3rd and 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement. 5th plug to circulate the rathole with 10 sx cement. Plug water well with 5 sx cement.

Remarks: Use 60/40 Pozmix, 2% gel, 3% cc. By Halliburton ticket No. 581246

I hereby certify that the above plugging instructions were given as herein stated and that I (did / did not) observe this plugging.

Signed Steve Rement (TECHNICIAN)

INVOICED RECEIVED STATE CORPORATION COMMISSION
DATE 2-1-84 INV. NO. 9302 WL
JAN 26 1984 CONSERVATION DIVISION Wichita, Kansas

1-26-84