

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-129-21893-00-00  
Spot: NE Sec/Twnshp/Rge: 36-34S-42W  
1323 feet from N Section Line, 1325 feet from E Section Line  
Lease Name: BENNETT B Well #: 8  
County: MORTON Total Vertical Depth: 3550 feet

Operator License No.: 33136  
Op Name: ANADARKO E & P ONSHORE LLC  
Address: PO BOX 1330  
HOUSTON, TX 77251

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		2750		WITH 10 SX CMT
PROD	5.5	3539	0	WITH 555 SX CMT
SURF	8.625	632		WITH 495 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/19/2015 8:30 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: DAVID RELEFORD Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 2750' WITH 10 SX CMT. PLUG AT 1450' WITH 30 SX CMT. CIRCULATE CMT TO SURFACE FROM 650'. TIE ONTO 8 5/8" & PUMP 10-25 SX CMT. PRESSURE TO 300#.

Plugging Proposal Received By: ROBERT DICKERSON Witness Type: NONE  
Date/Time Plugging Completed: 06/19/2015 12:00 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SET CIBP @ 2750' WITH 10 SX CMT. TOC 150' ON BOND LOG. PUMP 30 SX CMT AT 1450'. PUMP 75 SX CMT AT 650' TO SURFACE. PULL TBG & TOP OFF WITH 10 SX CMT. TIE ONTO 8 5/8" X 5 1/2" ANNULUS & PUMP 15 SX CMT. PRESSURE TO 300 PSI. LEFT BOTH SIDES FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
3174	3184		
3153	3157		
3101	3109		
3084	3095		
3051	3058		
3017	3020		
2982	2994		
2973	2977		
2894	2898		
2885	2886		
2874	2877		
2852	2855		
2839	2845		
2815	2825		
2803	3184		

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

7-6-15  
Received  
KANSAS CORPORATION COMMISSION  
JUL 06 2015  
CONSERVATION DIVISION  
WICHITA, KS  
7/8/15 CKM

District: 01

Signed Robert Dickerson  
(TECHNICIAN)

RECEIVED  
JUN 22 2015  
KCC DODGE CITY

SA