

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-159-21934-00-00
Spot: SWSESW Sec/Twnshp/Rge: 1-20S-6W
656 feet from S Section Line, 3308 feet from E Section Line
Lease Name: BRADEN B Well #: B-6
County: RICE Total Vertical Depth: 3400 feet

Operator License No.: 5920
Op Name: BANDY, TERRY P. DBA TE-PE OIL & G
Address: PO BOX 522
CANTON, KS 67428

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3399		150 SX
SURF	8.625	210		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/24/2015 9:30 AM
Plug Co. License No.: 30280 Plug Co. Name: SUNFLOWER WELL SERVICE, INC.
Proposal Rcvd. from: BUD DAVIS Company: SUNFLOWER WELL SERVICE, INC. Phone: (620) 628-4723

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JONATHAN HILL WitnessType: PARTIAL
Date/Time Plugging Completed: 06/24/2015 12:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

MIRU, CK BOTTOM. SAND EPRFS TO 3245' AND CAP WITH 5 SX'S CEMENT. CUT CASING OFF AT 850' AND PULL UP SOME AND PUMP 35 SX'S WITH 2% CC., PULL CASING ON UP TO 450' AND WAIT AWHILE. RUN BACK IN WITH DUMP BAIELR AND TAG CEMENT AT 800'. PUMP 35 SX'S CEMENT AT 450' THRU CASING, PULL CASING TO 260' AND CIRCUALTE CEMENT TO SURFACE. PULL CASING OUT AND TOP OFF.

Perfs:

Top	Bot	Thru	Comments
3303	3319	CSG	

6-30-15
KCC WICHITA
JUN 30 2015

Remarks: 60-40 POZ, 4% GEL QUALITY CEMENT #3657.

RECEIVED

Plugged through: CSG

7/8/15 CKM

District: 02

Signed

Virgil Clothier

(TECHNICIAN)

JK