

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-015-40211-00-00
Spot: SWSENW Sec/Twnshp/Rge: 11-27S-5E
3133 feet from S Section Line, 3357 feet from E Section Line
Lease Name: KNUTSON Well #: 2
County: BUTLER Total Vertical Depth: 2719 feet

Operator License No.: 5387
Op Name: THE BUCKEYE CORPORATION DBA A
Address: PO BOX 1020
EL DORADO, KS 67042

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	2692		50 SX
SURF	8.63	156		120 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/19/2015 8:00 AM
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.
Proposal Rcvd. from: STEVE KILE Company: AZTEC OIL CO. Phone: (316) 322-5776

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/19/2015 5:00 PM KCC Agent: DUANE KRUEGER

Actual Plugging Report:

RIH W/TBG @ 2636', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL 4% CC & DISPLACED IN CASING. WAITED 2 HOURS, TAGGED CEMENT @ 2529'. RIH W/ 1" TBG ON BACKSIDE OF 5 1/2" CSG @ 260', CONSOLIDATED MIXED & PUMPED 65 SXS 60/40 POZMIX 4% GEL TO SURFACE. LAYED DOWN 1" TBG. RIH W/1" TBG ON INSIDE OF 5 1/2" @ 260', CONSOLIDATED OIL WELL SERVICES MIXED & PUMPED 30 SXS 60/40 POZMIX 4% GEL TO SURFACE. CEMENT CIRCUALTED. PUMPED TOTAL 95 SXS 60/40 POZMIX 4% GEL CONSOLIDATED CEMENT TICKET #46159.

Perfs:

Top	Bot	Thru	Comments
2692	2719	OH	

Remarks:

Plugged through: TBG

7/8/15 CKM

District: 02

Signed

Duane Krueger

(TECHNICIAN)
KCC WICHITA

JUN 24 2015

Form CP-2/3

RECEIVED

6-24-15

IX