

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-21449-00-00
Spot: SWSESE Sec/Twnshp/Rge: 18-19S-28W
350 feet from S Section Line, 966 feet from E Section Line
Lease Name: HINEMAN B Well #: 2-18
County: LANE Total Vertical Depth: 4725 feet

Operator License No.: 5055
Op Name: C. H. TODD, INC.
Address: 1000 N TYLER STE 100
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4210		WITH 2 SX CMT
PROD	4.5	4729		625 SX
SURF	8.625	268		165 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/17/2015 12:00 PM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: DAVE PAULY Company: C.H. TODD Phone: (316) 250-2045

Proposed Plugging Method: SET CIBP @ 4210' WITH 2 SX CMT. RUN TBG TO 2130'. CIRCULATE CMT TO SURFACE. TIE ONTO BACKSIDE & CHECK BACKSIDE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/17/2015 2:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

SET CIBP @ 4210' WITH 2 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. HELD PRESSURE AT 200 PSI. RAN TBG TO 2110' & CIRCULATED CMT TO SURFACE WITH 150 SX CMT. PULLED TBG & PUMPED 50 SX CMT TO TOP OFF. CMT NEVER REACHED SURFACE. 6/22/15: ESTIMATED CMT AT 500'. TOPPED OFF WITH 35 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4541	4545		
4525	4531		
4337	4344		
4260	4264		

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

7/8/15 CKM

District: 01

Signed Larry Harris
(TECHNICIAN)

51A

RECEIVED
JUN 24 2015
KCC DODGE CITY

6-24-15

Received
KANSAS CORPORATION COMMISSION
JUL 06 2015
CONSERVATION DIVISION
WICHITA, KS