

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-175-10158-00-00  
Spot: NENE Sec/Twnshp/Rge: 9-35S-33W  
654 feet from N Section Line, 662 feet from E Section Line  
Lease Name: LIGHT Well #: 1-9  
County: SEWARD Total Vertical Depth: 6300 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		6078		WITH 2 SX CMT
PROD	4.5	6292	1795	WITH 200 SX CMT
SURF	8.625	1525		WITH 850 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/15/2015 10:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: DENNIS SPLAN Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: SET CIBP @ 6078' WITH 2 SX CMT. PLUG AT 1560' WITH 15 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/15/2015 1:30 PM KCC Agent: KENNY SULLIVAN

Actual Plugging Report:

SET CIBP @ 6078' WITH 2 SX CMT. 1ST PLUG AT 1570' WITH 15 SX GEL & 100 SX CMT. 2ND PLUG AT 662' WITH 50 SX CMT. 3RD PLUG AT 60' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
6128	6165		

Received  
KANSAS CORPORATION COMMISSION  
JUL 06 2015  
CONSERVATION DIVISION  
WICHITA, KS

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

Signed K/M

(TECHNICIAN)

RECEIVED  
JUN 30 2015  
KCC DODGE CITY

6-30-15