

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-24600-00-01
Spot: E2SWSWNW Sec/Twnshp/Rge: 31-11S-20W
2970 feet from S Section Line, 4800 feet from E Section Line
Lease Name: HUCK A Well #: 12
County: ELLIS Total Vertical Depth: 3968 feet

Operator License No.: 34506
Op Name: EMPIRE ENERGY E&P, LLC
Address: 345 RIVERVIEW ST., STE 540
WICHITA, KS 67203

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3972		275 SX
SURF	8.625	262		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/09/2015 12:00 AM
Plug Co. License No.: 33868 Plug Co. Name: RENEGADE WELL SERVICE, LLC
Proposal Rcvd. from: RANDY WEIGEL Company: EMPIRE ENERGY E&P, LLC Phone: (785) 737-3736

Proposed	06/09/2015- Ordered 385 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Plugging	06/10/2015- Ordered 150 sx 60/40 pozmix 4% gel 3% CC cement w/500 # hulls.
Method:	06/11/2015- Ordered 450 sx 60/40 pozmix 4% gel cement w/800 # hulls. Port Collar at 1702' cwc w/500 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/11/2015 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

06/09/2015- Shot packer off at 3400'. Ran tubing to 3380' and pumped 50 sx cement followed by 80 sx cement w/200 # hulls. Pulled tubing to 2100' and pumped 150 sx cement w/300 # hulls. Pulled tubing to 625' and pumped 100 sx cement. No returns, went on vacuum. Pulled all tubing. Hooked to braden head and pumped 5 sx cement.
06/10/2015-Ran tubing to 1500' and pumped 150 sx 60/40 pozmix 4% gel 3% CC and 500 # hulls. Backside blow then suck. Shut down.
06/11/2015- Ran tubing and tagged cement at 1750'. Pulled tubing to 1740' and pumped 75 sx cement w/200 # hulls. No circulation but good blow. Pulled tubing to 1140' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 625' and pumped 60 sx cement to circulate cement to surface. Topped off 5 1/2" casing w/15 sx cement.
GPS: 39.05255N -099.59206W

Perfs:

Top	Bot	Thru	Comments
3851	3855		
3562	3770		
3470	3496		

Remarks: QUALITY OILWELL CEMENTING TICKET #S 1161, 1456, 1457

Plugged through: TBG

7/8/15 ckm

District: 04

Signed Pat Bedore
(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

JUN 29 2015
CONSERVATION DIVISION
WICHITA, KS

6-29-15

JUN 22 2015