

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-20226-00-00
Spot: SE Sec/Twnshp/Rge: 29-30S-40W
1360 feet from S Section Line, 1261 feet from E Section Line
Lease Name: WARREN C. LYNN Well #: 1-29
County: STANTON Total Vertical Depth: 2350 feet

Operator License No.: 33646
Op Name: ENERGYPRO, INC.
Address: 500 S HANGAR DR
GEORGETOWN, TX 78628

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		696		
PROD	4.5	2350	0	WITH 200 SX CMT
SURF	8.625	649		WITH 385 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/08/2015 10:00 AM
Plug Co. License No.: 35195 Plug Co. Name: SURE ENERGY SERVICE, LLC
Proposal Rcvd. from: SAUL Company: SURE ENERGY SERVICE, LLC Phone: (806) 228-6049

Proposed Plugging Method: CIBP @ 1550' WITH 2 SX CMT. LOAD HOLE & PRESSURE TEST FOR LEAKS WITH 300 PSI. IF HOLDS PERFORATE @ 700' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: ROBERT DICKERSON Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/09/2015 10:00 AM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 20 SX CMT AT 1568'. CIBP @ 696'. ATTEMPT TO PRESSURE TEST CASING. WOULD NOT PRESSURE. GOT CIRCULATION OUT 8 5/8" OUTLET. BAD CASING ABOVE CIBP. PERFORATE 4 HOLES AT 675'. RUN PACKER & TUBING TO 375'. INJECTION RATE 2 1/2 BPM AT 100#. FULL CIRCULATION. PUMP 35 SX CMT THEN 10 7/8" BALL SEALERS & 50# HULLS, THEN 15 SX CMT. DISPLACE CMT TO 480'. PRESSURE TO 400#. 6/9/15: TAG CMT @ 480'. (15 SX INSIDE CASING & 35 SX OUTSIDE CASING). CIRCULATE CMT FROM 480' TO 0' INSIDE 4 1/2" CASING WITH 65 SX (35 SX WENT OUT CASING LEAKS IN 4 1/2" ABOVE 480'). TOP OFF 4 1/2" WITH 15 SX CMT. PUMP 40 SX CMT DOWN THE ANNULUS & FILL TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2250	2256		
2224	2232		

Received
KANSAS CORPORATION COMMISSION

JUL 06 2015

CONSERVATION DIVISION
WICHITA, KS

7-6-15

Remarks: USED CLASS C COMMON CEMENT BY SURE ENERGY.

Plugged through: TBG

District: 01

Signed

[Handwritten Signature]
5A

(TECHNICIAN)

7/8/15 ccm

RECEIVED
JUN 30 2015
KCC DODGE CITY