

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-04251-00-01  
Spot: SWSESE Sec/Twnshp/Rge: 22-12S-16W  
420 feet from S Section Line, 1041 feet from E Section Line  
Lease Name: GINTHER A Well #: 2  
County: ELLIS Total Vertical Depth: 3328 feet

Operator License No.: 33959  
Op Name: GINTHER OIL, INC.  
Address: 4612 188TH ST  
RUSSELL, KS 67665

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3408		175 SX
SURF	8.625	1073		150 SX

Well Type: EOR UIC Docket No: E27854.1 Date/Time to Plug: 06/24/2015 8:30 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: MILTON GINTHER Company: GINTHER OIL, INC. Phone: (785) 324-0491

Proposed Plugging Method: Ordered 425 sx 60/40 pozmix 4% gel cement, 5 sx gel and 600 # hulls.

Plugging Proposal Received By: RAY DINKEL Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 06/25/2015 12:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 1100' and 600'. Possible hole at 1450'. Ran tubing to 2820' and pumped 10 bbl of water, followed by 5 sx gel, followed by 75 sx cement w/100 # hulls. Pulled tubing to 1600' and pumped 100 sx cement w/300 # hulls. Pulled tubing to 600' and pumped 100 sx cement w/150 # hulls. Cement circulated out the backside with fluids circulating out braden head. POOH. Hooked to casing and pumped 80 sx cement to circulate cement out of the braden head. Pumped an additional 35 sx cement to balance out cement in casing. Cellar and casing were full of cement. Shut in.

GPS: 38.98826 -099.07943

Perfs:

Top	Bot	Thru	Comments
3295	3299		
2696	3299		

Received  
KANSAS CORPORATION COMMISSION  
JUL 06 2015  
CONSERVATION DIVISION  
WICHITA, KS  
7-6-15

Remarks: QUALITY CEMENTING TICKET # 1832

Plugged through: TBG

District: 04

Signed Ray AD - KED  
(TECHNICIAN)

CM

7/8/15 CKM

JUN 26 2015

UIC ✓