

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00625-00-00
Spot: NWNESW Sec/Twnshp/Rge: 23-30S-8W
2310 feet from S Section Line, 1650 feet from W Section Line
Lease Name: WEST SPIVEY UNIT Well #: 25
County: KINGMAN Total Vertical Depth: 4348 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 4900
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4347		275 SX
SURF	10.75	185		250 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/23/2015 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE Phone: (620) 425-1000

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: JEFF KLOCK WitnessType: PARTIAL
Date/Time Plugging Completed: 04/30/2015 2:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

NO PLUGGING RECORDS FOR THIS WELL BUT CEMENT AROUND HEAD WHEN DUG OUT. RAN SANDLINE INTO 270' TAGGED CEMENT. BROUGHT IN POWER SWIVEL & MUD PUMP SET BIT AND STARTED DRILLING, DRILLED FOR 4 + DAYS FROM 270' TO 780', DRILLED UP CEMENT WHOLE TIME. SWAGED UP AND PRESSURED UP TO 900 LBS HELD. WIRELINE PERFORATED AT 700' PRESSURED UP TO 900 LBS HELD AGAIN, WIRELINE PERFORATED AT 250', WIRELINE THEN LEFT LOCATION. TRIPPED TUBING INTO 700' PUMPED 80 SX COMMON CEMENT BRING TO SURFACE, TTO,. SWAGED UP AND PUMPED 15 SX AT 900 LBS HELD FOR HOUR. CEMENT ON BACK SIDE OF SURFACE PIPE.

Perfs:

Top	Bot	Thru	Comments
4292	4304		

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT, POWER SWIVEL AND PUMPS FOR JOB. WELL WAS FOUND ON WELL INVENTORY OF KCC DATA BAS WITH NO RECORDS.

Plugged through: TBG

7/8/15 CKM

District: 02

Signed *B. J. Hope*

(TECHNICIAN)
KANSAS CORPORATION COMMISSION

JUN 29 2015

Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

6-29-15

1/2