

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00896-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 23-30S-8W
2970 feet from S Section Line, 2310 feet from E Section Line
Lease Name: WEST SPIVEY UNIT Well #: 21
County: KINGMAN Total Vertical Depth: 4400 feet

Operator License No.: 33999
Op Name: LINN OPERATING, INC.
Address: 600 TRAVIS STE 4900
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	0	0		0 SX
PROD	5.5	4399		
SURF	0	0		0 SX
SURF	8.625	195		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 04/20/2015 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RANDY DICK Company: QUALITY WELL SERVICE Phone: (620) 425-1000

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON Witness Type: PARTIAL
Date/Time Plugging Completed: 04/22/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

WELL HAD BEEN SHUT IN SINCE 1985. FOUND PLUG AT APPROXIMATELY 635', RECORDS INDICATE A SQUEEZE JOB AT THAT DEPTH IN 1985, BUT NO RECORDS ABOUT DRILLING OUT THE CEMENT. RAN TUBING INTO WELL BORE TAGGED UP AT 625'. BROUGHT IN PUMP AND POWER SWIVEL, AND BEGAN DRILLING OUT WELL BORE, DRILLED THROUGH CEMENT APPROXIMATELY FEET, RAN TUBING INTO 4000' SPOTTED 35 SXS OF CEMENT AND 100 LBS HULLS & 3% CC., TAGGED TOP OF CEMENT @ 3516'. PERFORATED CASING AT 1286' WITH 4 SHOTS, AND AGAIN @ 255'. RAN TUBING INTO 1320' SPOTTED 35 SXS CEMENT & 50 LBS OF HULLS. PULLED TUBING TO 723' SPOTTED 35 SXS CEMENT, PULLED CASING TO 250' CIRCUALTED AROUND WITH 175 SXS CEMENT.

Perfs:

Top	Bot	Thru	Comments
4271			
3480'			
			740'

Remarks: COMMON CEMENT WAS USED FOR ENTIRE PLUGGING, PROVIDED BY QUALITY WELL SERVICE ALSO. WELL HAD BEEN ABANDONED SINCE 1985.

Plugged through: TBG

7/8 lbs cem

District: 02

Signed B. J. Hope

(TECHNICIAN)
KANSAS CORPORATION COMMISSION

JUN 29 2015

6-29-15
Form CP-2/3

CONSERVATION DIVISION
WICHITA, KS

JK