

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-187-20914-00-00
Spot: NWENW Sec/Twnshp/Rge: 16-30S-39W
4941 feet from S Section Line, 3660 feet from E Section Line
Lease Name: WINGER Well #: 1-316
County: STANTON Total Vertical Depth: 5780 feet

Operator License No.: 9810
Op Name: MCELVAIN ENERGY, INC.
Address: 1050 17TH ST STE 2500
DENVER, CO 80265

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4100		WITH 2 SX CMT
CIBP		5550		
PROD	4.5	5780	0	WITH 400 SX CMT
SURF	8.625	1777		WITH 750 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/19/2015 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: RODNEY GONZALEZ Company: MCELVAIN ENERGY Phone: (303) 962-6480

Proposed Plugging Method: CIBP @ 5550' WITH 2 SX CMT. CIBP @ 4100' WITH 2 SX CMT. PUMP 20 SX CMT AT 1800'. PERFORATE AT 650' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 06/19/2015 11:00 AM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 5550' WITH 2 SX CMT. CIBP @ 4100' WITH 2 SX CMT. PLUG AT 1800' WITH 20 SX CMT. PERFORATE AT 650' & CIRCULATED CMT TO SURFACE WITH 200 SX CMT. TOPPED OFF.

Perfs:

Top	Bot	Thru	Comments
5624	5678		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

7/8/15 CKM

District: 01

Signed [Signature] (TECHNICIAN)

RECEIVED
JUN 22 2015
KCC DODGE CITY

SA

KCC WICHITA
JUN 25 2015
RECEIVED

6-25-15