

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-23199-00-00
Spot: NESENE Sec/Twnshp/Rge: 17-9S-17W
3630 feet from S Section Line, 380 feet from E Section Line
Lease Name: KEAS Well #: 1-17
County: ROOKS Total Vertical Depth: 3508 feet

Operator License No.: 5205
Op Name: MID-CONTINENT ENERGY CORP.
Address: 105 S BROADWAY STE 360
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3493		150 SX
SURF	8.625	208		135 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/22/2015 10:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JEFFREY A. BURK, CONSU Company: MID-CONTINENT ENERGY CORP Phone: (316) 250-5655

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 400 # hulls and 15 sx gel.
Production perforations: 3446' - 3503'
DV Tool did not circulate
Perforated at 705', cwc witnessed by Carl Goodrow

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/22/2015 12:30 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3448' and pumped 15 sx gel followed by 50 sx cement w/200 # hulls. Pulled tubing to 1463' and pumped 180 sx cement w/200 # hulls to circulate cement to surface. Pulled all tubing and topped off 5 1/2" casing w/30 sx cement. Visually checked annulus and cement to surface.

GPS: 39.27331N -099.23428W

Perfs:

Top	Bot	Thru	Comments
3493	3503		
3446	3450		

Remarks: QUALITY WELL SERVICE, INC. TICKET # 6354

Plugged through: TBG

7/8/15 ckm

District: 04

Signed Pat Bedore
(TECHNICIAN)

cm

JUN 22 2015

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUN 29 2015
CONSERVATION DIVISION
WICHITA, KS

6-29-15