

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21917-00-00
Spot: NW Sec/Twnshp/Rge: 31-21S-31W
3967 feet from S Section Line, 3792 feet from E Section Line
Lease Name: WIDOWS Well #: 1-31
County: FINNEY Total Vertical Depth: 2822 feet

Operator License No.: 31652
Op Name: NORSTAR PETROLEUM, INC.
Address: 88 INVERNESS CIR. E. UNIT F104
ENGLEWOOD, CO 80112

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2816	0	WITH 335 SX CMT
SURF	8.625	429		WITH 275 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/01/2015 11:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: DAVID Company: SWIFT SERVICES, INC. Phone: (785) 798-2300

Proposed Plugging Method: PUMP 150# HULLS WITH FIRST SX CMT. FILL WITH CMT TO SURFACE. CHECK BACKSIDE.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/01/2015 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

FILL 4 1/2" CASING WITH CMT FROM 2718' TO 0' USING 150# HULLS & 165 SX CMT. PRESSURE TO 600#. HOLDING. PUMP 15 SX CMT DOWN THE ANNULUS TO 300#.

Perfs:

Top	Bot	Thru	Comments
2708	2718		

Received
KANSAS CORPORATION COMMISSION
JUL 06 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: **COMPLIANCE ISSUE: DENIED TA LACK OF LEASE** USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: CSG

7/8/15 CKM

District: 01

Signed Ken Jehlik
(TECHNICIAN)
5/18

RECEIVED
JUN - 5 2015
KCC DODGE CITY