

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-007-22390-00-01
Spot: NWNWSE Sec/Twnshp/Rge: 27-30S-12W
2335 feet from S Section Line, 2255 feet from E Section Line
Lease Name: MEAIRS B Well #: 1
County: BARBER Total Vertical Depth: 4710 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		4000		WITH 2 SX CMT
CIBP		4450		
CIBP		4640		
PROD 4.5		4705	3193	WITH 275 SX CMT
SURF 8.625		247		WITH 180 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/18/2015 3:20 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 4000' WITH 2 SX CMT. PLUG AT 750' WITH 50 SX CMT. PLUG AT 270' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 06/18/2015 4:10 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

SET CIBP @ 4000' WITH 2 SX CMT. 1ST PLUG AT 761' WITH 15 SX GEL & 50 SX CMT. 2ND PLUG AT 285' WITH 50 SX CMT. 3RD PLUG AT 63' WITH 60 SX CMT. CMT CIRCULATED.

Perfs:

Top	Bot	Thru	Comments
4304	4316		

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

7/8/15 cem

District: 01

Signed _____

KCC WICHITA (TECHNICIAN)

RECEIVED
JUN 22 2015
KCC DODGE CITY

JUN 25 2015
RECEIVED

6-25-15