

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-00060-00-00
Spot: SWSWNE Sec/Twnshp/Rge: 34-30S-9W
2310 feet from N Section Line, 2310 feet from E Section Line
Lease Name: KEIMIG Well #: 1
County: KINGMAN Total Vertical Depth: 4430 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	4429	2041	100 SX
SURF	8.625	120		125 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 06/01/2015 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Revd. from: BARRY Company: ALLIANCE WELL SERVICE Phone: (620) 793-2316

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 05/27/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 4317' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 2041' PULLED CASING. TRIPPED TUBING INTO 1455' SPOTTED 35 SX CEMENT. TRIPPED TUBING OUT TO 945' SPOTTED 35 SX CEMENT. TRIPPED TUBING OUT TO 255' CIRCUALTED TO SURFACE WITH 118 SX CEMENT.

Perfs:

Top	Bot	Thru	Comments
4367	4377		

Remarks: ALLIED CEMENT OUT OF GREAT BEND, PROVED CEMENT - COMMON #% CC

Plugged through: TBG

7/8/15 CKM

District: 02

Signed *B. J. Hope*

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUN 29 2015

CONSERVATION DIVISION
WICHITA, KS

6-29-15

JK