

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-21216-00-00
Spot: W2E2NW Sec/Twnshp/Rge: 35-30S-9W
1320 feet from N Section Line, 1880 feet from W Section Line
Lease Name: LEE Well #: 2
County: KINGMAN Total Vertical Depth: 4490 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4486		125 SX
SURF	8.625	216		180 SXS CMT
SURF	8.625	218		180 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 05/26/2015 12:00 AM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY Company: ALLIANCE WELL SERVICE Phone: (620) 793-2316

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 05/20/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 4355' CAPPED WITH 2 SX CEMENT ON TOP. CUT CASING PIPE OFF @ 3421' PULLED CASING. TRIP TUBING INTO 1478' SPOTTED 35 SX OF CEMENT. TTO TO 932' SPOTTED 35 SX OF CEMENT. TTO TO 257', CIRCULATED TO SURFACE WITH 71 SX OF CEMENT.

Perfs:

Top	Bot	Thru	Comments
4410	4420		

Remarks: ALLIED OUT OF GREAT BEND WAS CEMENTERS - COMMON CEMENT WITH 3% CC WAS USED FOR PLUG JOB. TICKET #65549.

Plugged through: TBG

7/8/15 CKM

District: 02

Signed B. J. Hope

(TECHNICIAN)

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUN 29 2015

CONSERVATION DIVISION
WICHITA, KS

6-29-15

1/K