

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

AUG 2 - 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Dave Austin of Cities Service Oil Co. has this date requested permission to plug the following described well:

Mr. Austin guarantees payment of the plugging fee.

Operator's full Name: Cities Service Oil Company

Complete Address: Box 308, Great Bend, Kansas

Lease Name: Fincham "D" Well No. # 1

Location: C SE SE NW Sec. 1 Twp. 29 Rge. 13 (E) (W) W

County Pratt Total Depth 4760' Oil Well       

Gas Well        Input Well        SWD Well        D & A X Lost Hole       

Mr. Austin was instructed to plug the well as follows:

961' of 8 5/8" surface pipe, cement circulated with 500 sacks.  
~~XXXXXXXX~~ Fill hole with drilling mud to 300', 1st cementing plug,  
bridge with hulls, and cement with 25 sacks. Fill hole with drilling  
mud to 40', 2nd cementing plug, bridge with hulls, and cement with  
10 sacks to base cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

*Archie Elving*