

State of Kansas



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

19-January 8 '82

RECEIVED
STATE CORPORATION COMMISSION

FEB - 2 1982
CONSERVATION DIVISION
Wichita, Kansas

2-2-82

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

Dear Sir:

Mr. Albert Wursch of Kelso Casing Plugging has this date requested permission to plug the following described well:

Operator's Full Name: J. Mark Richardson
Complete Address: 640 Century Plaza Bldg Wichita Kansas 67202
Lease Name: Robbins Well No. 1
Location: C-SE-SW Sec. 3 Twp. 29S Rge. 16W(E) (W)
County: Kiowa Total Depth: 4750
Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: This well was completed but not produced

Mr. Wursch was instructed to plug the well as follows:

There is 515' of 8 1/2" surface casing cement circulated with 100 lbs of cement. They ran 4749' of 4 1/2" production pipe cemented with 27 lbs of 60/40 spag cement. The perforations were set from 4458' to 4720'. 1st plug they sandbed bottom back with 4 lbs of cement on top bringing top to 4400'. 2nd plug they pumped 5 lbs hulls, 20 lbs of fill, 50 lbs cement, 5 lbs of fill. Then they released

Very truly yours,

Raul Luthie
Conservation Division Agent

(over)

rubber plug a pumped 100 lbs. of cement on top of
it. They recovered 3630' of 4 1/2" production pipe. The
plugging was accomplished by Halliburton Co out
of Pratt Kansas. The cement used was 50/50 grade
with 2 3/4 yds of 3% C.C. The well was shut in at 400 lbs.
pressure.