

15-097-00197-00-00

State of Kansas

FORM - CP-2



JOHN ANDERSON, Jr. Governor  
RICHARD C. BYRD Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
CHARLES C. McCARTER Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 3 1962

CONSERVATION DIVISION  
Wichita, Kansas

12-3-62

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Nov. 27, 1962

Dear Sir:

Mr. Jack Ensminger of Leben Drilling Co. has this date requested permission to plug the following described well:

Mr. Jack Ensminger guarantees payment of the plugging fee.

Operator's full Name: Sol Robinowitz

Complete Address: 311 Shell Bldg. Tulsa, Oklahoma.

Lease Name: Lanier #1 Well No. #1

Location: C-NW-SW Sec. 7 Twp 29S Rge. 16 (E) (W) X

County Kiowa Total Depth 4825' Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Jack Ensminger was instructed to plug the well as follows:

309' of surface pipe circulated with cement. Hole filled to 180' with heavy drill mud, 1/4 sack hulls, 1st cementing plug, and 20 sacks cement. Hole filled to 40' with heavy drill mud 1/4 sack hulls, 2nd cementing plug and 10 sacks cement to base of cellar. Rat. hole bridged and 2 sacks cement.

Very truly yours,

*Herman J. Justice*  
Conservation Division Agent