

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

MAY 14 1971

CONSERVATION DIVISION
Wichita, Kansas

5-14-71

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Freeman of Garvey Drlg. Co. has this

date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.Operator's full Name: Allen & ParkerComplete Address: Box 906 Perryton, TXLease Name: Laurence Schwarm Well No. 1Location: 1470' WEL & 1170' SNL Sec. 2 Twp. 29s Rge. 18 (E)(W) WCounty: Kiowa Total Depth 4972 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Freeman was instructed to plug the well as follows:395 ft of 8 5/8 surface pipe cemented with 325 sacks. Pump40 sacks cement to 600 ft. Fill hole to 370 ft, pump 30sacks cement. Mud to 40 ft, 1/2 sack hulls, plug, 15 sackscement to surface. 3 sacks cement in rat hole, 3 sackscement in mouse hole.Halliburton Cementing Co. Great Bend, Ks
Very truly yours,

Conservation Division Agent