



JOHN CARLIN
R. C. LOUX
JANE T. ROY
PHILLIP R. DICK
CAROL J. LARSON

Governor
Chairman
Commissioner
Commissioner
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

200 Colorado Derby Building
WICHITA, KANSAS 67202

21 April 1982

RECEIVED
STATE CORPORATION COMMISSION

APR 27 1982

CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To be filed by Plugging Agent)

15-097-20867-0006

4-27-82

Dear Sir:

Mr. E. J. Woody of H-30 Drilling Co. Inc. has this date requested permission to plug the following described well:

Operator's Full Name: Cinco Exploration Co.

Complete Address: Box 2723, Victoria, Texas 77901

Lease Name: Freda Dunbar Well No. 2

Location: C-NW-NE Sec. 1 Twp. 29 Rge. 16 (E) (W)

County: Kiowa Total Depth: 4800'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereafter indicated: _____

Mr. Woody was instructed to plug the well as follows:

They cement circulated 414' of 8 5/8" surface casing. 1st plug at 900' with 100 Sbk of cement. 2nd plug at 400' with 40 Sbk of cement. 3rd plug 40' to 0' with 10 Sbk of cement. Then circulated 10 Sbk cement in rat hole & 5 Sbk of cement in mouse hole. The cement was pumped through drill pipe with hole full of heavy mud. The plugging was accomplished by Halliburton Co.

Very truly yours,

Raul A. Luthi
Conservation Division Agent