


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kingman County. Sec. 5 Twp. 27S Rge. 6 XX W (W)
Location as "NE/CNW/SW" or footage from lines C SE SE
Lease Owner MACK OIL CO.
Lease Name Biggs Well No. 1
Office Address 812 Union Center Bldg., Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed September 29 19 67
Application for plugging filed September 29 19 67
Application for plugging approved September 29 19 67
Plugging commenced September 30 19 67
Plugging completed September 30 19 67
Reason for abandonment of well or producing formation Dry

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas
Producing formation None Depth to top _____ Bottom _____ Total Depth of Well 4100 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|------|--------|------------|
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged with 30 sax common cement @ 240'
25 sax common cement @ 50' to top
5 sax common cement in rathole
Plugging completed: September 30, 1967 @ 2:30 p.m.

RECEIVED
STATE CORPORATION COMMISSION
OCT 4 1967

CONSERVATION DIVISION
WICHITA, KANSAS

10-4-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor MACK OIL CO.
Address P. O. Box 400, Duncan, Oklahoma 73533

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Robert L. Harris (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert L. Harris
812 Union Center Building, Wichita, Kansas 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of October, 19 67

My commission expires September 21, 1968

Elizabeth F. Nice
Elizabeth F. Nice Notary Public.

RECEIVED
WATER CONSERVATION COMMISSION
OCT 4 1967

CONSERVATION DIVISION
Wichita, Kansas

MACK OIL CO.
Duncan, Oklahoma

DRILLERS WELL LOG

#1 Biggs C SE SE - Section 5-27S-6W
Kingman County, Kansas
Commenced R. D.: 9-18-67 Elevation: 1509' Kelly Bushing
Completed R. D.: 9-29-67 Initial Production: Dry
Rotary Total Depth: 4100' Contractor: Mack Oil Co.

| STRATA | DEPTH |
|-----------------|-----------------------------------|
| Top Soil & Sand | 0 - 45' |
| Red Bed & Shale | 45 - 250' |
| Lime & Shale | 250 - 580' |
| Shale & Shells | 580 - 1436' |
| Lime & Shale | 1436 - 1900' |
| Shale & Lime | 1900 - 2124' |
| Shale & Shells | 2124 - 2513' |
| Lime | 2513 - 2755' |
| Lime & Shale | 2755 - 2974' |
| Lime | 2974 - 3423' |
| Lime & Shale | 3423 - 3653' |
| Lime | 3653 - 3745' |
| Chat | 3745 - 3822' |
| Lime | 3822 - 3849' |
| Lime & Chert | 3849 - 3916' |
| Cherty Lime | 3916 - 3981' |
| Lime | 3981 - 4100' - Rotary Total Depth |

I hereby certify that the above is a true and correct log of said well as reflected by the daily drilling reports.

MACK OIL CO.

By Robert L. Harris
Robert L. Harris

Signed and sworn to in my presence this 2nd day of October, 1967, by Robert L. Harris, representative of Mack Oil Co.

Elizabeth F. Nice
Elizabeth F. Nice, Notary Public

My commission expires September 21, 1968