


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County, Sec. 28 Twp. 27 Rge. 5 (E) W (W)



Location as "NE/CNW&SW" or footage from lines C SW/4
Lease Owner Drillers Production Company, Inc.
Lease Name Opdike Well No. 1
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10-8-64 _____ 19____
Plugging completed 10-13-64 _____ 19____
Reason for abandonment of well or producing formation Depleted.

Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Justus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3786 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|-------------------|------------------|------------|
| | | | | 8-5/8" | 252' | None |
| | | | | 4-1/2" | 3786' | |
| | | | | 4-1/2" | 3768' | 3325' |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3786', sanded hole to 3760' and dumped 3 sacks of cement @ 3760' with dump bailer. Pulled 4 1/2" casing, mudded hole to 250', set rock bridge to 240' and dumped 25 sacks of cement @ 240'. Mudded hole to 40', set rock bridge to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1964

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

10-28-64

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight

(employee of owner) or (conservation operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 20th day of October, 1964

My commission expires May 20, 1968
Milton J. Volin
Notary Public.

GABBERT-JONES DRILLING CO., INC.

WICHITA, KANSAS

DRILLER'S WELL LOG

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1964

OPDYKE #1
C SW SECTION 28-27S-5W
KINGMAN COUNTY, KANSAS

CONSERVATION DIVISION
Wichita, Kansas

COMMENCED: JULY 25, 1960
COMPLETED: AUGUST 3, 1960

OPERATOR: DRILLERS PRODUCTION CO., INC.

| DEPTH | | FORMATION | REMARKS |
|-------|------|---|---|
| FROM | TO | | |
| 0 | 65 | SURFACE CLAY, SAND & REDBED REDBED & SHALE | RAN 252' OF 8-5/8" CASING, CEMENTED @ 251' W/225 SACKS CEMENT. |
| 65 | 252 | | |
| 252 | 735 | SHALE | RAN 116 JOINTS OF 4 1/2" CASING, CEMENTED @ 3768 1/2' W/100 SACKS CEMENT. |
| 735 | 770 | LIME | |
| 770 | 1075 | SHALE & SHELLS | |
| 1075 | 1260 | SHALE & LIME | |
| 1260 | 1400 | LIME | |
| 1400 | 3235 | LIME & SHALE | |
| 3235 | 3495 | LIME | |
| 3495 | 3725 | LIME & SHALE | |
| 3725 | 3763 | SHALE | |
| 3763 | 3769 | LIME | |
| 3769 | TD | | |

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE OPDYKE #1 WELL.

E. E. HALL

STATE OF KANSAS }
COUNTY OF SEDGWICK } SS

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 8TH DAY OF AUGUST, 1960, PERSONALLY APPEARED E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES: OCTOBER 2, 1963.