


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Kingman County. Sec. 28 Twp. 27 Rge. 5 (E) W (W)
Location as "NE/CNW&SW" or footage from lines. C SW SW
Lease Owner Drillers Production Company, Inc.
Lease Name Opdike Well No. 2
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 10-14-64 _____ 19____
Plugging completed 10-16-64 _____ 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was com-
menced? yes

Name of Conservation Agent who supervised plugging of this well Justus
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3782 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	250'	None
				4-1/2"	3782'	3348'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3780', sanded hole to 3760' and dumped 3 sacks of cement @ 3760' with dump bailer. Pulled 4 1/2" casing, mudded hole to 260', set rock bridge and dumped 25 sacks of cement @ 250'. Mudded hole to 40', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

OCT 28 1964

PLUGGING COMPLETE.

CONSERVATION DIVISION
Wichita, Kansas

10-28-64

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 20th day of October, 1964

My commission expires May 20, 1968

Milton J. Volin
Notary Public.

GABBERT-JONES DRILLING CO., INC.

WICHITA, KANSAS

DRILLER'S WELL LOG


OPDYKE #2
C SW SW SECTION 28-27S-5W
KINGMAN COUNTY, KANSAS

COMMENCED: SEPTEMBER 20, 1960
COMPLETED: ~~SEPTEMBER 20, 1960~~ October 8, 1960

OPERATOR: DRILLERS PRODUCTION Co., Inc. Elevation 1461 RB

<u>DEPTH</u>		<u>FORMATION</u>	<u>REMARKS</u>
FROM	TO		
0	40	SURFACE SOIL AND SAND	
40	250	RED BED & SHALE	RAN 253.52' OF 8-5/8" CASING, CEMENTED @ 250' WITH 225 SACKS CEMENT
250	790	SHALE & SHELLS	
790	825	ANHYDRITE	Lansing 2978
825	3160	SHALE & LIME	Miss Chert 3760
3160	3228	LIME	Miss Dolo 3780
3228	3758	LIME & SHALE	RTD 3782
3758	3780	CHELT	TD 3792
3780	3782	DOLOMITE	
3782	RD		RAN 3782' OF 4-1/2" CASING, CEMENTED W/ 100 SACKS CEMENT.

I, E. E. HALL, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S WELL LOG FOR THE OPDYKE #2 WELL.


E. E. HALL

STATE OF KANSAS }
 } SS
COUNTY OF SEDGWICK }

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 3RD DAY OF OCTOBER, 1960 PERSONALLY APPEARED, E. E. HALL TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.


VIRA A. MCKENZIE, NOTARY PUBLIC

MY COMMISSION EXPIRES OCTOBER 2, 1963
Drill cement and drill deeper 3782-91
Frac 5000 Acid Petrofrac + 5000 sand
Flow 34 BO + 80 BW + 1650 MCFGD
Workover 1-27-61 to 2-3-61
Squeeze cement
Clean out and drill deeper 3791-92
2500 Acid
240 BHPD + slight show oil + good show gas
Plug back 3775
Perf 16/s 3764-68
222 BHPD + very slight show oil + good show gas