

WICHITA MAR 7 1966

Form CP-4


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sedgwick County, Sec. 31 Twp. 27 Rge. 4 (E) W (W)

Location as "NE/CNWxSWx" or footage from lines SE NE SW
Lease Owner The Shallow Water Refining Company
Lease Name Bartholomew Unit, Tract 14 Well No. 6
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 2-24-66 _____ 19____
Plugging completed 3-1-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3754 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	202'	None
				5-1/2"	3746'	3118'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3754', sanded hole to 3740' and dumped 5 sacks of cement @ 3740' with dump bailer. Pulled 5 1/2" casing, set rock bridge @ 205' and dumped 20 sacks of cement. Mudded hole to 35', and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION
MAR 8 1966

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY (If additional description is necessary, use BACK of this sheet)
Address CHASE, KANSAS 3-8-66

STATE OF KANSAS, COUNTY OF RICE, ss. Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 4th day of March, 1966

My commission expires May 20, 1968 Milton J. Volin Notary Public.

Bartholomew Unit Tract 14 North

KANSAS GEOLOGICAL BUREAU -- KANSAS GEOLOGICAL SOCIETY

308 EAST MURDOCK - WICHITA, KANSAS

COPY 6

Shallow Water Drilling

COMPANY WESTGATE - GREENLAND OIL CO.

SEC. 31 T. 27 R. 47

LOC. SE NE SW

FARM Davis

NO. 6

TOTAL DEPTH 3754

COMM. 7-6-50

COMP. 7-29-50


SHOT OR TREATED

CONTRACTOR Jackson Drilling Corp.

ISSUED 11-4-50

COUNTY Sedgwick

KANSAS



8 5/8" 202' core w/135 sx.
5 1/2" 3746' core w/75 sx.

ELEVATION 1412

PRODUCTION Pot. 277 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS

cellar	9
clay & shale	50
shale & shells	470
lime & shale	688
salt	690
salt, lime & shale	825
lime & shale	1086
shale	1145
lime	1285
lime & shale	1475
shale	1562
shale & lime	2300
lime	2525
lime & shale	2861
brn lime	2871
lime & shale	2905
lime	2955
lime & shale	2980
lime	3375
shale & lime	3649
shale	3686
lime, shale & sand	3705
Miss. lime cherty	3735
lime	3754
Total Depth	
Tops:	
Brown lime	2857
Lansing	2887
Mississippi	3707

RECEIVED
STATE CORPORATION COMMISSION
FEB 10 1966
CONSERVATION DIVISION
Wichita, Kansas

750 gals. Dowell Service 1000 gals.
additional flowing 25 bbls. oil per hr.
Measurements from top of derrick floor.