



STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County, Sec. 31 Twp. 27 Rge. 4 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW NE SW
Lease Owner The Shallow Water Refining Company
Lease Name Tract 14 Well No. 3
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 1-12-66 _____ 19____
Plugging completed 1-17-66 _____ 19____
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above
Section Flat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3744 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	213'	None
				5-1/2"	3730'	2265'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole to 3744', sanded hole to 3720' and dumped 5 sacks of cement @ 3720' with dump bailer. Pulled 5 1/2" casing, set rock bridge @ 200' and dumped 20 sacks of cement. Mudded hole to 35', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

FEB 1 1966

CONSERVATION DIVISION
Wichita, Kansas

PLUGGING COMPLETE.

2-1-66

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (~~OWNER~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 29th day of January, 19 66

My commission expires May 20, 1968

Milton J. Volcan
Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SURVEY
 503 E. Mirock, Wichita, Kansas


Tract 14

Company - WESTGATE GREENLAND OIL CO.
 Firm - Davis No. 3

SEC. 31 T. 27 R. 17
 NW NE SW

Total Depth. 3744
 Comm. 4-21-50 Comp. 5-1-50
 Shot or Traced
 Contracted. Jackson Drilling
 Issued. 6-17-50

County. Sedgwick
 KANSAS



CASINGS:
 10 3/4" 213' cem w/135 sx.
 5 1/2" 3730' cem w/75 sx.

Elevation.
 Production. Pot. 412 bbls.

Figures Indicate Bottom of Formations.

shale, shells	445
salt, shale	545
shale, shells w/lime	700
lime, shale	910
shale, lime shells	1065
lime, shale	1155
lime, shale brks	1315
lime, shale	1645
shale, shells	1815
shale, limestrks	2015
lime, shale	2380
lime, shale brks	2535
lime, shale	2650
lime	2700
limeshale	2820
lime, shale brks	2925
lime	3055
limeshale	3105
lime	3230
lime w/lime brkn	3290
lime	3355
shale	3415
shale, lime strks	3515
lime, shale	3670
lime	3725
lime cherty	3744
Total depth	
Tops:	
Mississippi	3710

RECEIVED
 STATE COMMODATION COMMISSION
 NOV 23 1965
 RESERVATION DIVISION
 Wichita, Kansas