

WICHITA JAN 3 1965

15-173-01592-0000

69

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

Sedgwick County, Sec. 31 Twp. 27 Rge. 4 (E) W (W)

Location as "NE/CNW/SW" or footage from lines NW SW SW
Lease Owner The Shallow Water Refining Company
Lease Name Tract 14 Bartholomew 14 Well No. 4
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 12-18-65 _____ 19____
Plugging completed 12-22-65 _____ 19____
Reason for abandonment of well or producing formation Depleted

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3775 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	203'	None
				5-1/2"	3766'	3331'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole, sanded hole to 3760' and dumped 5 sacks of cement @ 3760' with dump bailer. Pulled 5 1/2" casing, set rock bridge from 200' to 185' and dumped 20 sacks of cement @ 185'. Mudded hole to 30' and ran 10 sacks of cement to base of cellar.

RECEIVED
STATE CORPORATION COMMISSION

JAN 4 1966

CONSERVATION DIVISION
WICHITA, KANSAS

PLUGGING COMPLETE.

1-4-66

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
Noel J. Knight (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30th day of December, 1965

My commission expires May 20, 1968

Milton J. Volin
Notary Public.


31-27-4W
Trach 14

Company - WESTGATE GREENLAND OIL CO.
Farm - Davis No. 4

SEC. 31 T. 27
NW SW SW

Total Depth. 3775
Comm. 5-3-50 Comp. 5-19-50
Shot or treated.
Contractor. Jackson Drilling Corp.
Issued. 6-24-50

County. Sedgwick
KANSAS



CASING:

8 5/8" 203' cem w/135 ex.
5 1/2" 3765' cem w/75 ex.

Elevation. _____
Production. Pot. 3000 bbls.

Figures Indicate Bottom of Formations.

MEAS. FROM TOP OF DERRICK FLOOR.

- shale, shells 430
- salt, shale, shells 560
- shale, limshells 625
- lime, shale 725
- anhyd. 765
- lime, shale brks 890
- lime, shale 1660
- lime shells, shale 1715
- shale, lime strks 1965
- lime, shale 2335
- lime, lime brkn 2465
- lime, shale 2650
- lime w/brkn lime 2750
- lime, shale 2910
- lime 3366
- shale 3400
- lime strks, shale 3458
- lime, shale 3720
- shale, lime sand 3728
- Miss. lime cherty 3757
- lime cherty 3775
- Total depth

Tops:
Lansing 2909
Mississippi 3726

RECEIVED
STATE CORPORATION COMMISSION
NOV 23 1965
CONSERVATION DIVISION
Wichita, Kansas