

STATE OF KANSAS
STATE CORPORATION COMMISSION


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD



Sedgwick County, Sec. 31 Twp. 27 Rge. 4 W (W)

Location as "NE/CNW/SW" or footage from lines NE NW SW
Lease Owner Shallow Water Refining Company
Lease Name Bartholmew TR14-1W Well No. _____
Office Address Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 9/23/67 19____
Plugging completed 9/30/67 19____
Reason for abandonment of well or producing formation depleted.



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3751' Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	188'	none
				5-1/2"	3735'	3140'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Checked hole and ran 1000# sand, checked hole and ran another 1000# sand. Loaded hole with water. Checked hole, found sand bridged at 1788', worked pipe and cleaned cellar. Pumped sand bridge out, set 5 sacks of cement. Shot pipe at 3245', worked pipe. Shot at 3150', spotted 60 barrels oil, worked pipe loose and pulled 98 joints. Set rock bridge at 240' and ran 5 yards of ready mix. Tallied pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

OCT 5 1967

CONSERVATION DIVISION
Wichita, Kansas

10-5-67

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight
CHASE, KANSAS
(Address)

SUBSCRIBED AND SWORN TO before me this 3rd day of October, 19 67

My commission expires February 15, 1971
Margaret Melcher Notary Public.

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY

508 E. Murdock, Wichita, Kas


COPY
Trach 14
2.47
W1

Company - WESTGATE GREENLAND OIL CO.
Farm - Davis No. 1

SEC. 31 T. 27
NE NW SW

Total Depth. 3751
Comm. 2-23-50 Comp. 3-20-50
Shot or Treated. 1000 gals.
Contractor. Jackson Drilg.
Issued. 6-17-50

County. Sedgwick
KANSAS



CASING:
10 3/4" 188' cem w/175 sx.
5 1/2" 3735' cem w/75 sx.

Elevation. _____

Production. Post. 1109 bbls.

Figures Indicate Bottom of Formations.

MEASUREMENTS FROM TOP DERRICK FLOOR.

shale, shells	450
salt, shale	685
lime, shale	2990
lime	3225
lime, shale	3270
lime	3350
lime, shale	3700
shale	3703
lime Miss.	3725
lime	3751
Total depth	

Tops:	
Lansing	2889
Mississippi	3701

RECEIVED
STATE CONSERVATION COMMISSION

AUG 23 1967

CONSERVATION DIVISION
Wichita, Kansas