

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Sedgwick County, Sec. 31 Twp. 27 Rge. 4 (E) W (W)

Location as "NE/CNW&SW" or footage from lines SW NW SW  
Lease Owner The Shallow Water Refining Company  
Lease Name Tract 14 Well No. 2  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 12-23-65 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 12-29-65 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3765 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				9-5/8"	189'	None
				5-1/2"	3760'	3227'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3765', sanded hole to 3750' and dumped 5 sacks of cement @ 3750' with dump bailer. Pulled 5 1/2" casing, set rock bridge @ 190' and dumped 20 sacks of cement. Mudded hole to 40', set rock bridge and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

JAN 10 1966

CONSERVATION DIVISION  
Wichita, Kansas

1-10-66

PLUGGING COMPLETE

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner/operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of January, 1966

My commission expires May 20, 1968  
Milton J. Holm Notary Public.

WELL BUREAU -- KANSAS GEOLOGICAL SURVEY  
 508 E. Murdock, Wichita, Kansas

COPY


31-27-4E

Company - WESTGATE-GREENLAND OIL CO.  
 Farm - Davis No. 2

SEC. 31 T. 27 R. 14W  
 SW NW SW

Total Depth. 3765  
 Comm. 4-7-50 Comp. 4-28-50  
 Shot or Treated. Acid  
 Contractor. Jackson Drilling Co.  
 Issued. 6-3-50

County. Sedgwick  
 KANSAS



CASING:  
 9 5/8" 189' cem. w/125 sx.  
 5 1/2" 3760' cem. w/75 sx.

Elevation. \_\_\_\_\_

Production. Pot. 1920 bbls.

Figures Indicate Bottom of Formations.

shale & shells	695
lime & shale	1350
lime	1455
lime & shale	1650
shale & shells	1845
lime & shale	2300
lime & lime brkn	2455
lime w/shale brkn	2545
lime & shale	2630
lime	2755
lime & shale	2865
shale	2902
lime	3076
lime & shale	3150
lime	3355
lime & shale	3566
shale	3630
lime	3645
shale	3655
shale, lime strks	3723
lime Miss.	3752
cherty lime	3765
Total Depth	

Tops:  
 Miss. 3716

Acidized w/1000 gals.

MEASUREMENTS FROM TOP OF DERRICK FLOOR.

RECEIVED  
 STATE CORPORATION COMMISSION  
 NOV 23 1965  
 INSPECTION DIVISION  
 Wichita, Kansas