

PR

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Sedgwick County, Sec. 31 Twp. 27 Rge. 4 (E) (W)

Location as "NE/CNW/SE/SW" or footage from lines SE NW NW

Lease Owner Shallow Water Refining Company

Lease Name Bartholmew TR8 Well No. 2

Office Address Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole)

Date well completed 19

Application for plugging filed 19

Application for plugging approved 19


Plugging commenced 9/9/67 19

Plugging completed 9/13/67 19

Reason for abandonment of well or producing formation depleted

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes



Locate well correctly on above Section Flat

Name of Conservation Agent who supervised plugging of this well Justice

Producing formation Depth to top Bottom Total Depth of Well 3740 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	215'	none
				5-1/2"	3733'	2967'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Sanded hole to 3730', set 5 sacks of cement. Loaded hole with water. Shot pipe at 2975', worked pipe loose and pulled 90 joints. Mudded hole to 300', set 20' rock bridge and ran 4 1/2 yards ready mix. Talled pipe.

PLUGGING COMPLETE.

RECEIVED
STATE CORPORATION COMMISSION

SEP 19 1967

CONSERVATION DIVISION
Wichita, Kansas

9-19-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY

Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss. NOEL J. KNIGHT

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight

CHASE, KANSAS

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of September, 19 67

My commission expires February 15, 1971

Margaret Melcher
Notary Public.

Log No. 2 Well

ENCILED

ORIGINAL

Sheet 8 #2

Location in the NW, NW, NOV 25 1950

Section 31-27S-6W,
Sedgwick County, Kansas

Drilled for: Kingwick Oil & Gas Co., Inc.
Drilled by: Beardmore Drilling Company

SE NW NW

Casing Records:

BHB 1110 lbs.

8-5/8" 215'
5-1/2" 3753'

Drilling Commenced: May 21, 1950.
Drilling Completed: June 3, 1950.

FORMATION	DEPTH
Cellar	5
Shale - Sand - Shells	70
Shale - shells	(215
Shale - shells)	760
Shale - lime	(1170
Lime - shale	1355
Shale - lime	2225
Lime - shale	2605
Shale - lime	2715
Lime - shale	2800
Shale - lime	2900
Lime	3320
Lime - shale	(3625
Shale - lime	3675
Shale	3698
Cherty lime	3730
Lime - dolomite	3740 T. D.

6 12-50 lbs.
1000 gals. acid
1414 lb Elev.
Zaps. Sec.
ML 3698
Dols. 3732

RECEIVED
STATE CORPORATION COMMISSION

AUG 23 1967

STATE OF KANSAS
COUNTY OF SEDGWICK

CONSERVATION DIVISION
Wichita, Kansas

I, the undersigned, being duly sworn on oath state that the above and within statement is a true and correct record and log of the well drilled on the location above-described, to the best of my knowledge and belief.

Handwritten signature

Subscribed and sworn to before me this 14th day of June, 1950.

My Commission Expires:
November 1, 1953.

Notary Public