

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County, Sec. 31 Twp. 27 Rge. 4 (E) W (W)

Location as "NE/CNW%SW%" or footage from lines NW NW SE  
Lease Owner Shallow Water Refining Company  
Lease Name Bartholomew Unit, Tract 15 Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 3-2-66 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed: 3-7-66 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3736 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	187'	None
				5-1/2"	3726'	2274'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3736', sanded hole to 3725' and dumped 5 sacks of cement @ 3725' with dump bailer. Pulled 5 1/2" casing, set rock bridge @ 200' and dumped 20 sacks of cement. Mudded hole to 35', and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

MAR 18 1966

CONSERVATION DIVISION  
Wichita, Kansas

PLUGGING COMPLETE.

3-18-66

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KX KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or ~~Conservation Director~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 16th day of March, 1966

My commission expires May 20, 1968

Milton J. Volin  
Notary Public.

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY *Tract 15*  
 508 East Murdock, Wichita, Kansas


COPY  
 09

Company: L. B. STABLEFORD  
 Form: Dieffenbacher No. 1  
*Bartholomew Unit Tract 15 #1*

SEC. 31 T. 27 R. 4W  
 NW NE

Total Depth. 3736  
 Comm. 5-2-50 Comp. 5-17-50  
 Shot or Treated.  
 Contractor.  
 Issued. 7-22-50

County: Sedgwick  
 KANSAS



CASING:  
 8 5/8" 187' cem w/150 sx.  
 5 1/2" 3726' cem w/100 sx.

Elevation. \_\_\_\_\_

Production. 398 bbls.

Figures Indicate Bottom of Formation:

red bed	196
shale, shells	535
salt	570
shale, shells	815
lime, shale	1020
lime	1040
lime, shale	1796
shale, shells	1940
lime shells, shale	2085
lime, shale	2325
lime	2370
lime, shale	2915
lime	3379
lime, shale	3550
lime	3612
lime, shale	3689
lime	3736
Total depth	
Tops:	
Brown Lansing	2843
Lansing	2874
Mississippi	3689

Show Oil 3718-24, 3727-36'

RECEIVED  
 LATE CORPORATION COMMISSION  
 FEB 10 1966  
 CONSERVATION DIVISION  
 Wichita, Kansas