

9


STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

WELL PLUGGING RECORD

Sedgwick County, Sec. 31 Twp. 27 Rge. 4 ~~W~~ (W)

Location as "NE/CNW/SW" or footage from lines NW SW SE  
Lease Owner Shallow Water Refining Company  
Lease Name Bartholmew TR16 #1 Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 11/6/67 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 11/9/67 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation depleted.



If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Scott  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3756 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10"	217'	none
				7"	3747'	2305'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 1900' and found bridge, pushed bridge to 3000'.  
Ran sand to 2980' and dumped 6 sacks of cement. Loaded hole, shot pipe at 2524', 2442', 2362' and 2307', pipe came loose. Pulled pipe.  
Checked fluid to 350', mudded to 250', set 20' rock bridge and dumped 5 yards of ready mix.

PLUGGING COMPLETE.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 14 1967

CONSERVATION DIVISION  
WICHITA, KANSAS

11-14-67

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY, INC.  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
NOEL J. KNIGHT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel Knight  
CHASE, KANSAS  
(Address)

SUBSCRIBED AND SWORN to before me this 10th day of November, 19 67

My commission expires February 15, 1971

Margaret Melcher  
Notary Public.


WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

*Track 16*  
**COPY**

Company - W. C. MCBRIDE, INC.  
Farm - Dieffenbacher No. 1

SEC. 31 T. 27 R. 4W  
NW SW SE  
330' fr. 1/4, 990  
fr. 3/4 of SE/4  
County, Sedgwick  
KANSAS

Total Depth. 3756 RB  
Comm. 6-9-50 Comp. 7-21-50  
Shot or Treated. 1000 gal. acid 3747-3754  
Contractor. Jackson  
Issued. 9-22-51.



CASING:  
10" 217' cem.  
6 5/8" OD 3747' cem.

Elevation. 1115 DE  
Production. 298 BO, 20% wtr.

Figures indicate Bottom of Formations.

clay	40
clay, sand, shells	217
shale, shells	450
salt, shale	610
shale, shells	710
lime, shale	3040
lime	3086
lime, shale	3225
lime	3285
lime, shale	3309
lime	3350
shale	3410
shale, lime	3680
lime, chert	3723
cherty lime	3746
lime	3756 RB
Total depth	

Tops:  
Mississippi line 3706-3754

Scout tops:  
Brown Line 2857

**RECEIVED**

AUG 23 1967

CONSERVATION DIVISION  
Wichita, Kansas

