

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Form CP-4


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Sedgwick County, Sec. 31 Twp. 27 Rge. 4 (E) W (W)

Location as "NE/CNW/SW" or footage from lines SE SW SE  
Lease Owner The Shallow Water Refining Company  
Lease Name Bartholomew Unit, Tract 16 Well No. 2  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 3-16-66 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 3-22-66 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Paul Turpin  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3769 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	209'	None
				7"	3758'	3103'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3769', sanded hole to 3750' and dumped 5 sacks of cement @ 3750' with dump bailer. Pulled 7" casing, checked fluid to 495' mudded hole to 215', set rock bridge to 200' and dumped 20 sacks of cement @ 200'. Mudded hole to 20' and ran 10 sacks of cement to base of cellar.

RECEIVED  
STATE CORPORATION COMMISSION

PLUGGING COMPLETE.

MAR 29 1966

3-29-66

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS, COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or ~~owner or operator~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 25th day of March, 19 66

Milton J. Tolie

My commission expires May 20, 1968

Notary Public.

Tract 16  
COPY

Company - W. C. MERRIDE, INC.  
Farm - T. of Seneca No. 2

SEC. 31 T. 27 R. 14W  
SE SW SE

Bartholomew Unit Tract 16 # 2

Total Depth 3769

Comm. 3-25-51

3-31-51


County, Sec. 31

KANSAS

Shot or Vented

Contractor - Price Drlg. Co. & Jackson Drlg. Corp.

Issued 7-7-51



Elevation 1110 L.S.F.

Casing:  
10 3/4" 209' cem.  
7" 3758' cem.

Production 496 BO

Figures Indicate Bottom of Formations.

surface soil sand & shale	209
shale & shells	425
shale & salt	595
shale & lime	2245
shale	2260
shale & lime	2900
lime	3255
shale & lime	3724
chat	3768
T.D. Derrick Floor	3766'
chat	3769
Total Depth	

Tops:	
Brown Lime	2862
Lansing K.C.	2903
Miss. Lime	3724

3-29-51 Acidized with 1000 gal. acid; Swabbed in, flowed 55 B.O. in 2 hrs. 3-3-51  
 4-11-51 Flow for 12 hrs. first 6 hrs. 159 B.O. Second 6 hrs. 134 B.O.  
 4-25-51 State Productivity 496 B.O. (flowing)  
 DST: 3768, packer 3758' open 30 min. fair steady blow. rec. 2400' gas, 120' gas & oil cut mud.  
 SIP, 15 min. 1375#.

Drillers log. Measurement from rotary bushing.

RECEIVED  
STATE CORPORATION COMMISSION

FEB 10 1966

CONSERVATION DIVISION  
Wichita, Kansas